

**TABLE 1A-2  
Locations of Pipelines and Aboveground Facilities**

Pipeline Segment	Facility	Length (miles)	Location (MP)	Horsepower	Comments
<b>Supply Laterals:</b>					
Sherwood Lateral	Pipeline	54.0	--	--	New 36-inch-diameter pipeline
	Sherwood Compressor Station Sherwood Meter Station Pig trap SW-MLV-01	--	0.00	14,205	New compressor station New receipt meter station within compressor station site Launcher Mainline Valve
	CGT Tie-In Site	--	0.21	--	Tie-in with CGT Lateral (also listed on CGT Lateral)
	SW-MLV-02	--	16.54	--	Mainline Valve
	SW-MLV-03	--	29.13	--	Mainline Valve
	SW-MLV-04	--	35.34	--	Mainline Valve
	SW-MLV-05	--	42.55	--	Mainline Valve
	Sherwood Tie-In Site Pig trap SW-MLV-06	--	52.31	--	Tie-In with Seneca Lateral (also listed on Seneca Lateral) Receiver Mainline Valve
CGT Lateral	Pipeline	5.7	--	--	New 24-inch-diameter pipeline
	CGT Tie-In Site Pig trap CGT-MLV-01	--	0.00	--	Tie-in with Sherwood Lateral (also listed on <b>Sherwood</b> Lateral) Launcher Mainline valve
	CGT Meter Station Pig trap CGT-MLV-02	--	5.68	--	New delivery meter station Receiver Mainline Valve
Seneca Lateral	Pipeline	25.7	--	--	New 42-inch-diameter pipeline
	Seneca Compressor Station Seneca Meter Station Rex Meter Station Pig trap SN-MLV-01	--	0.00	18,940	New compressor station New receipt meter station New delivery meter station Launcher Mainline Valve

**TABLE 1A-2  
Locations of Pipelines and Aboveground Facilities**

Pipeline Segment	Facility	Length (miles)	Location (MP)	Horsepower	Comments
Seneca Lateral	Hall Meter Station	--	3.67	--	New receipt meter station
	Sherwood Tie-In Site SN-MLV-02	--	16.65	--	Tie-in with Sherwood Lateral (also listed on Sherwood Lateral) Mainline Valve
	Gulfport Meter Station	--	21.88	--	New receipt meter station
	SN-MLV-03	--	25.63	--	Mainline Valve (Within Clarington Compressor Station)
Berne Lateral	Pipeline	4.2	N/A	--	New 24-inch-diameter pipeline
	Berne Meter Station Pig trap BN-MLV-01	--	0.00	--	New receipt meter station Launcher Mainline Valve
	Pig trap BN-MLV-02	--	3.69	--	Located with the Seneca Compressor Station Mainline Valve within Seneca Compressor Station
Clarington Lateral	Pipeline	32.8	N/A	--	New 42-inch-diameter pipeline
	Clarington Compressor Station Four (4) meter stations	--	0.35	11,245	New compressor station Two receipt and two bidirectional meter stations
	Majorsville Tie-In Site CL-MLV-01	--	11.75	--	Tie-In with Majorsville Lateral (also listed on Majorsville Lateral) Mainline Valve
	CL-MLV-02	--	21.57	--	Mainline Valve
	Cadiz Tie-In Site Pig trap CL-MLV-03	--	32.84	--	Tie-in with Cadiz Lateral and Supply Connector (also listed on those laterals) Receiver Mainline Valve
Majorsville Lateral	Pipeline	23.7	--	--	New 24-inch-diameter pipeline
	Majorsville Meter Station Pig trap MJ-MLV-01	--	0.0	--	New receipt meter station Launcher Mainline Valve
	Majorsville Compressor Station MJ-MLV-01	--	1.14	7,100	New compressor station Mainline Valve

**TABLE 1A-2  
Locations of Pipelines and Aboveground Facilities**

Pipeline Segment	Facility	Length (miles)	Location (MP)	Horsepower	Comments
Majorsville Lateral	Side Tap	--	4.31	--	Future connection
	MJ-MLV-02	--	10.63	--	Mainline Valve
	MJ-MLV-03	--	14.07	--	Mainline Valve
	Majorsville Tie-In Site Pig trap MJ-MLV-04	--	23.55	--	Tie-In with Clarington Lateral (also listed on Clarington Lateral) Receiver Mainline Valve
Cadiz Lateral	Pipeline	3.4	--	--	New 30-inch-diameter pipeline
	Cadiz Compressor Station Two (2) Meter Stations Pig trap CD-MLV-01	--	0.00	15,980	New compressor station Two new receipt meter stations Launcher Mainline Valve
	Cadiz Tie-In Site Pig trap CD-MLV-02	--	3.4	--	Tie-in with Clarington Lateral and Supply Connector (also listed on those laterals) Receiver Mainline Valve
Supply Connector Lines A and B	Supply Connector Line A	18.6	--	--	New 42-inch-diameter pipeline
	Supply Connector Line B	18.6	--	--	New 42-inch-diameter pipeline
	Cadiz Tie-In Site Pig trap MLA MLV-01 & MLB MLV-01	--	0.00	--	Tie-in with Clarington Lateral and Cadiz Lateral (also listed on those laterals) Launcher Mainline Valves (2)
	MLA MLV-01 & MLB MLV-02	--	10.09	--	Mainline Valves (2)
	Burgettstown Tie-In Site	--	48.38	--	Tie-in with Burgettstown Lateral (also listed on Burgettstown Lateral)
Burgettstown Lateral	Pipeline	51.7	--	--	New 36-inch-diameter pipeline
	Burgettstown Compressor Station Burgettstown Meter Station Pig trap BG-MLV-01	--	0.00	5,175	New compressor station New receipt meter station Launcher Mainline Valve

**TABLE 1A-2  
Locations of Pipelines and Aboveground Facilities**

Pipeline Segment	Facility	Length (miles)	Location (MP)	Horsepower	Comments
Burgettstown Lateral	BG-MLV-02	--	12.52	--	Mainline Valve
	BG-MLV-03	--	17.96	--	Mainline Valve
	BG-MLV-04	--	35.10	--	Mainline Valve
	BG-MLV-05	--	43.09	--	Mainline Valve
	Burgettstown Tie-In Site Pig trap BG-MLV-06	--	51.69	--	Tie-in at Mainline Compressor Station 1 Receiver Mainline Valve
<b>Mainlines:</b>					
Mainlines A and B	Mainline A	190.9	--	--	New 42-inch-diameter pipeline
	Mainline B	183.6	--	--	New 42-inch-diameter pipeline
	Mainline Compressor Station 1 Burgettstown Lateral Tie-In Site Side Tap MLA MLV-03 & MLB MLV-03		18.77	42,190	New compressor station Tie-in 24-inch future connection Mainline Valves (2)
	MLA MLV-04 & MLB MLV-04	--	36.84	--	Mainline Valves (2)
	Crossover Valve MLA MLV-05 & MLB MLV-05	--	49.91	--	Midpoint 36-inch crossover valve between pipelines Mainline Valves (2)
	MLA MLV06 & MLB MLV-06	--	61.11	--	Mainline Valves (2)
	MLA MLV-07 & MLB MLV-07	--	73.95	--	Mainline Valves (2)
	Mainline Compressor Station 2 Pig trap MLA MLV-08 & MLB MLV-08 Pig trap	--	77.3	38,745	New compressor station Receiver Mainline Valves (2) Launcher
	MLA MLV-09 & MLB MLV-09	--	77.60	--	Mainline Valves (2)
	MLA MLV-10 & MLB MLV-10	--	90.95	--	Mainline Valves (2)
	Crossover Valve MLA MLV-11 & MLB MLV-11	--	102.12	--	Midpoint 36-inch crossover valve between pipelines Mainline Valves (2)
	MLA MLV-12 & MLB MLV-12	--	118.32	--	Mainline Valves (2)

**TABLE 1A-2  
Locations of Pipelines and Aboveground Facilities**

Pipeline Segment	Facility	Length (miles)	Location (MP)	Horsepower	Comments
Mainlines A and B	Mainline Compressor Station 3 Pig trap MLA MLV-13 & MLB MLV-13 Pig trap MLA MLV-14 & MLB MLV-14	--	127.9	34,010	New compressor station Receiver Mainline Valves (2) Launcher Mainline Valves (2)
	MLA MLV-15 & MLB MLV-15	--	144.33	--	Mainline Valves (2)
	Crossover Valve MLA MLV-16 & MLB MLV-16	--	157.58	--	Midpoint 36-inch crossover valve between pipelines Mainline Valves (2)
	MLA MLV-17 & MLB MLV-17	--	174.13	--	Mainline Valves (2)
	Side Tap - Dual	--	185.5	--	Future connection
	MLA MLV-18 & MLB MLV-18	--	189.80	--	Mainline Valves (2)
	Mainline B Tie-In Site Pig trap MLA MLV-19 & MLB MLV-19	--	202.06	--	Receiver at end of Line B Receiver Mainline Valves
	Mainline A	ANR Meter Station	--	208.86	--
Pig trap PEPL Meter Station MLA MLV-20		--	209.20 209.3	--	Receiver at Defiance Compressor Station New delivery meter station Mainline Valve at Defiance Compressor Station
Market Segment		Pipeline	100.0	N/A	N/A
	Defiance Compressor Station Pig trap MKT-MLV-01	--	0.00	25,830	New compressor station Launcher Mainline Valve
	MKT-MLV-02	--	17.15	--	Mainline Valve
	MKT-MLV-03	--	30.67	--	Mainline Valve
	MKT-MLV-04	--	48.94	--	Mainline Valve
	MKT-MLV-05	--	58.86	--	Mainline Valve

**TABLE 1A-2  
Locations of Pipelines and Aboveground Facilities**

Pipeline Segment	Facility	Length (miles)	Location (MP)	Horsepower	Comments
Market Segment	Consumers Energy Meter Station MKT-MLV-06	--	75.03	--	New delivery meter station Mainline Valve
	MK-MLV-07	--	81.03	--	Mainline Valve
	MK-MLV-08	--	87.87	--	Mainline Valve
	MK-MLV-09	--	98.77	--	Mainline Valve
	Vector Meter Station Pig trap	--	100.0	--	New delivery meter station Receiver
	MKT-MLV-09				Mainline Valve